

BILL OF QUANTITIES (BOQ)

Name of work : CONSTRUCTION OF HOUSPITAL BUILDING AT GOVT. SCHOOL ROAD
JAKKUR IN WARD NO 05. JAKKUR.

Sl. No.	Approved Qty.	Description	Unit	Issued to	
				Technical Manager , KRIDL	
				In Figures	In Words
1	40.00	KSRB2-1.2 Earthwork in surface excavation ordinary soil for leveling and lowering the ground (other than foundation of buildings, culverts, road drains and trenches for pipe lines and cables) and removing the excavated stuff to a distance not exceeding 50m and lift upto 1.50m excavated surface levelled and neatly dressed, disposed earth to be levelled after breaking of and neatly dressed as per specification. Specification NO KBS 2.1(b)/2.3.1 Page No-5 item No 2.1 Page No 5	Cum	169.56	Rupees One Hundred Sixty Nine and Fifty Six Paise Only
2	51.34	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5 Item No 2.4 Page No 5	Cum	305.64	Rupees Three Hundred Five and Sixty Four Paise Only
3	7.86	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Item No 4.3 Page No 12.	Cum	5256.36	Rupees Five Thousand Two Hundred Fifty Six and Thirty Six Paise Only
4	16.27	KSRB 5.2-3 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammerdressed in courses not less than 20 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Item No 5.6 Page No 23.		4521.96	Rupees Four Thousand Five Hundred Twenty One and Ninety Six Paise Only
5	14.84	KSRB 5.3-3 : Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 Item No 5.9 Page No 23.		5405.40	Rupees Five Thousand Four Hundred Five and Forty Paise Only

Signature of the contractor
EXECUTIVE ENGINEER-4
KRIDL, BBMP DIVISION
BENGALURU-560 010

24/12
Executive Engineer

S.No.	proved Qty.	Description	Unit	Issued to	
				Technical Manager , KRIDL	
				In Figures	In Words
6	27.24	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of Design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @ 0.460 cum, with super plasticisers @ 3 liters conforming to IS 9103-1999 re-affirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation for footings, pedestals, retaining walls, return walls, walls (any thickness) including attached pilasters, column pillars, posts, struts, buttresses, bed blocks, anchor blocks & plinths etc., including cost of all materials, labour, HOM of machinery, curing, complete but excluding cost of reinforcement as per specifications. Specification No. KBS 4.1, 4.6 Item No 4.11	Cum	6491.88	Rupees Six Thousand Four Hundred Ninety One and Eighty Eight Paise Only
7	18.78	KSRB 2.6 : Providing and filling sand in foundation upto plinth to required depth for sub soil treatment including watering ramming with all lead and lift complete as per specifications. specification. No. KBS 2.10.2 Item No 2.13 Page No 6.	Cum	2305.80	Rupees Two Thousand Three Hundred Five and Eighty Paise Only
8	187.81	KSRB 5-14 : Providing and constructing precast concrete solid blocks with compressive strength not less than 3.5 Newton per sqmm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. Item No 5.27. Page No 25	Sqm	979.56	Rupees Nine Hundred Seventy Nine and Fifty Six Paise Only
9	6.91	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 - TMT bars Fe 500 Item No 4.46.1	Sqm	60534.00	Rupees Sixty Thousand Five Hundred Thirty Four Only
10	3.78	Supplying and fixing pressed steel door frames size 125x65 mm manufactured from 1.25mm thick carbon steel or imported steel strips with mitred joints of 900 for door openings and shutters made out of seasoned Honne wood, styles of 30 mm, thick with lock rail of 160 mm, width, top and side rails of 100 mm. width and bottom rails of 250 mm width and panel filling with 12mm thick particle board of exterior grade bonded with phenol formaldehyde resin and the shutter shall be rot proof, vermin proof, heat resistant guaranteed against shrinkage, warpage and such other defects for a period of 3 years. This shall be as per approved drawings, specification and direction including cost of conveyance, manufacturing, painting with enamel paint 2 coats over primer coat, cost of labour for all items of work, machinery, equipment and all other incidental charges with all lead, lift, loading and unloading etc., complete. The Hollow portion of the frame to be filled with cement concrete 1:2:4. Page No 40 Item No 7.26	Sqm	3780.00	Rupees Three Thousand Seven Hundred Eighty Only

S.No.	Approved Qty.	Description	Unit	Issued to	
				Technical Manager, KRIDL	
				In Figures	In Words
11	9.99	"Supplying and fixing pressed steel window frame of size 100 x 50mm manufactured from 1.25 mm thick carbon steel or imported steel strips with neat mitred joints at 90degree for window openings and shall be suitable to fix M.S. grills as per design and drawings using 12mm dia rods at 100mm Centre to Centre horizontally and two members of M.S flats of 6mmx40mm size at 150mm apart, welded into a frame of 6mmx40mm size M.S. flats with 16mm size lugs, and 8 Nos. of 100mm size hinges, 4 Nos of Butt Stay pins and 4 Nos. Tower bolts and shutters half panelled and half glazed with shutters made out of seasoned honne wood, styles of 30mm thick and 100mm width and rails of 30mm thick and 100mm width and using 4mm thick pin headed glass and panel, filling with 12mm thick particle board of exterior grade bonded with phenol formal dehide resin and the shutter shall be rot proof vermin proof, heat resistant guaranteed against shrinkage, warp age and such other defects for a period of 3 years.This shall be as per approved drawing, specification and direction including cost of conveyance, manufacturing painting with 2		4104.00	Rupees Four Thousand One Hundred Four Only
12	99.035	KSRB 4-6.2 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for flat surface such as roofs, landings, balconies and likes, thickness upto 200 mm including cost of all materials, labour complete as per specifcations.up to 3.50m from Ground level. Specification No. KBS 4.6.2 Item No 4.18 page No 15		338.04	Rupees Three Hundred Thirty Eight and Four Paise Only
13	45.16	KSRB 4-6.7 :Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for sides and soffits of beams, beam haunchings, cantilever girders, bressumers and lintels not exceeding 1m in depth including cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Item No 4.34 Page No 16		276.48	Rupees Two Hundred Seventy Six and Forty Eight Paise Only
14	90.44	KSRB15-3-13 : Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to ceiling including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Item No 15.21 page No 114.		208.44	Rupees Two Hundred Eight and Forty Four Paise Only
15	263.13	KSRB 15.3.1 Providing 12mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Item No 15.9 Page No 113.		195.48	Rupees One Hundred Ninety Five and Forty Eight Paise Only
16	353.57	KSRB15-7 : Providing lime rendering for plastering to wall and ceiling, including cost of materials, labour, curing complete as per specifications. Item No 15.33 Page No 115		27.00	Rupees Twenty Seven Only
17	176.90	KSRB15-3.4 : Providing 15mm thick cement plaster in single coat with cement mortar 1:3, to brick masonry including rounding off corners wherever required smooth rendering, : Providing and removing scaffolding, including cost of materials, labour, curing complete as per specifications. Item No 15.12 page No 113		221.40	Rupees Two Hundred Twenty One and Forty Paise Only

S.No.	Approved Qty.	Description	Unit	Issued to	
				Technical Manager, KRIDL	
				In Figures	In Words
18	8.09	KSRB 4-1.4 : Providing and laying in position plain cement concrete of mix 1:5:10 with OPC cement @ 160kgs, with 40mm and down size graded granite metal coarse aggregates @0.86cum and fine aggregates @ 0.58cum machine mixed, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Item No 4.4 Page No 12.		5099.76	Rupees Five Thousand Ninety Nine and Seventy Six Paise Only
19	9.65	Providing and fixing colour glazed tiles all sizes 10mm thick for flooring trades of steps and landing laid on a bed of 12mm thick cement mortar 1:3 mix Flush pointing using white cement with Matching colour pigment including cost of materials labours curing complete as per specification Item No 14.36.1 Page No 106		999.00	Rupees Nine Hundred Ninety Nine Only
20	32.20	KSRB 14-17.2 : Providing skirting, dado, rises of steps with colour glazed tiles on 10mm thick cement plaster 1:3 and jointed with white cement slurry over rough plaster surface (excluding cost of rough plastered surface which should be measured and paid separately) using glazed tiles of approved make and size including cost of materials, labour, complete as per specifications. Specification No.KBS 14.16, 14.17 - Colour glazed tiles 15x15 cms 6mm thick Item No 14.41.1 Page No 106		1157.76	Rupees One Thousand One Hundred Fifty Seven and Seventy Six Paise Only
21	353.57	KSRB 15-14.1 : Providing and applying two coats with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after thoroughly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. Item 15.49.1 Page No 117.		76.68	Rupees Seventy Six and Sixty Eight Paise Only
22	176.90	KSRB 15-16.1 : Providing and finishing external walls in two coats with waterproof cement paint of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications. Item No 15.53.1		90.72	Rupees Ninety and Seventy Two Paise Only
23	20.00	KSRB 11-2 : Providing and fixing white vitreous china clay, water closet Orissa pattern of size 580 x 440mm with integral type footrests, 100mm S or P trap, 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I / M.S brackets, 32mm diameter flush pipe fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 Item No 12.2 Page No 77.		4682.88	Rupees Four Thousand Six Hundred Eighty Two and Eighty Eight Paise Only

S.No.	Approved Qty.	Description	Unit	Issued to	
				Technical Manager , KRIDL	
				In Figures	In Words
24	3.00	KSRB 11-7.1 : Providing and fixing white vitreous china clay, flat back, lipped front urinal basin of 430x260x350mm with 5 litres PVC automatic flushing cistern, C.I / M.S brackets, standard flush pipe and C.P. brass spreaders with brass unions and G.I. clamps complete painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 Item No 12.7 _Page No 78.		4456.08	Rupees Four Thousand Four Hundred Fifty Six and Eight Paise Only
25	3.00	KSRB 11-11.1 : Providing and fixing white vitreous china clay, flat back wash basin size 630x450mm with a pair of 15mm C.P brass pillar taps with C.I / M.S brackets, 32 mm C.P. brass waste of standard pattern, painting of fittings and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11 Item No 12.23 Page No 80.		4196.88	Rupees Four Thousand One Hundred Ninety Six and Eighty Eight Paise Only
26	50.00	KSRB13-1.1 : Providing and fixing to wall, ceiling and floor galvanised / mild steel tube 15mm dia nominal bore with fittings (medium grade weight 1.27 kg/mtr) B class including cost of all materials, labour charges, HOM of equipments and testing complete as per specifications. Specification No.KBS 13.2.14 / 13.8 Item No 13.1 Page No 90		199.80	Rupees One Hundred Ninety Nine and Eighty Paise Only
27	1000.00	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer Black or Blue and inner White layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications. Item No 37.58. Page No 265.		6.48	Rupees Six and Forty Eight Paise Only
28	10.00	KSRB13-6.2-2 : Providing and fixing in position brass stop cock of approved quality 20mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3 Item No 13.27		158.24	Rupees One Hundred Fifty Eight and Twenty Four Paise Only

1. The work should be executed as per the specification and standard specified by the PWD & Other specifications of the
2. The work should be carried out as per the directions and instructions of the concerned Engineer
3. The Contractor should maintain the quality of work as per the standard specifications.

Cleauda 24/03
 Executive Engineer (Byatarayanapura)
 Bruhath Bangalore Mahanagara Palike

I am prepared to take up the above work at the rates quoted by me in the Schedule 'B'.

[Signature]
 CONTRACTOR
 EXECUTIVE ENGINEER
 KRIDL, BBMP DIVISION
 BENGALURU-560 010